

G.R. 130

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any)

Official Number.	Name of Ship.	No., Date, and Port of Registry.
164428	ITALIA CAESAR	15/1937 Grimsby

No., Date, and Port of previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Single Screw	Beverley	1937	Cook, Welton & Gemmell Ltd., Beverley.
Number of Decks	One	Length from fore part of stem, to the aft side of the head of the stern post		Feet. 173 Tenths. 0
Number of Masts	Two	Main breadth to outside of plank		28 6.5
Rigged	Ketch	Depth in hold from tonnage deck to ceiling amidships		14 6.5
Stem	Raked	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards		
Stern	Cruiser	Depth from top of deck at side amidships to bottom of keel		
Build	Clencher	Round of beam		7
Framework and description of vessel	Steel Trawler	Length of engine room, if any		36 0
Number of Bulkheads	5 Watertight			

Particulars of propelling Engines, etc., (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Estimated Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Reciprocating Steam Triple Expansion Direct Acting Vertical.	British	1937	Amos & Smith Ltd., Hull.	Three 15"	27"	-	N. H. P. 156.2 I. H. P. 1100
No. of Shafts.	Particulars of Boilers.		When made.	Name and address of makers.	No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	Estimated Speed of Ship.
One	Description	Boilers.						
	Single ended Multitubular	Boilers.	1937	Amos & Smith Ltd., Hull.	42"			12 1/2 Knots
	Number							
	One							
	Iron or Steel							
	Steel							
	Loaded Pressure							
	220 lbs.							


Number of water ballast tanks, and their capacity in tons:— One - 14 3/4 Tons.

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	462.84	On account of space required for propelling power	203.79
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind, not being the personal property of the Crew	-
Turret or Trunk		These spaces are the following, viz. :-	
Forecastle (House in)	4.85	Nil	
Bridge space	12.02	(Number of seamen or apprentices for whom accommodation is certified.....)	
Deck Break	8.77	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :-	
Side Houses	29.62	Master's Accommodation 13.04	
Round Houses		Chart Space 2.50	
Chart House		Wireless Telegraphy Space 3.58	31.58
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		Boatswain's Store 8.01	
Excess of Hatchways		Water Ballast Spaces 4.45	235.37
		Total	
Gross Tonnage	518.10	Cubic Metres. 1466.22	
Deductions, as per contra	235.37	666.09	
Register Tonnage	282.73	800.13	

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 116.45 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 25.65 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.
Forecastle, Length 34.3' = 26.28 Tons.



Name of Master W. Martin

Certificate of Service Competency No. 12018

No. of Owners


Name, Residence, and Description of Managing Owner if there are more owners than one.

The Earl Steam Fishing Company Limited, Fish Docks, Grimsby, Lincolnshire.

Sir Alec Black, Bt., Field House, Grimsby.

Sixty four (64/64) Shares.

Dated 7th July, 1937.



Mr. Soden



© 2021

Lloyd's Register
Foundation