

PIPING ARRANGEMENT Endorsement.

Shipbuilders: ~~Messrs.~~

s/s "Helle"

~~Yard No.~~

Engineers: ~~Messrs.~~

Oil Fuel Conversion

~~Engine No.~~

It is submitted that the *plan of piping arrangements* merits approval, provided the arrangements be as shown and amended on the plan and the remaining requirements of the Rules for Pumping and Piping be complied with so far as they are applicable.

It is noted that the P+S storage tanks are filled separately through 6" connections at the top of the tanks and since it appears probable that the filling hose will be led to only one tank at a time it is strongly recommended that the cross-connection line leading from each tank to the transfer pump be not less than about 4 1/2" bore so that the tanks ^{could} maintain similar levels while filling.

Return

2 plans (to Stockholm)

Retain

1 copy

~~Advise~~

no 1/10

~~Freeboard.~~



© 2020

Lloyd's Register
Foundation

PHH
WRE
30 SEP 1952