


RD REPORT on the S.S. "Marguerite".

It is submitted the Surveyor be informed that it is concluded that the portable plates stated on his report to be fitted to openings in the bulkhead at front of Raised Quarter Deck are actually fitted to openings in the bulkhead at aft end of Bridge and that the Raised Quarter Deck bulkhead is intact but he should conform this and state if the bolts pass through the bulkhead plating.

The Surveyor should also report the spacing of the bolts securing the portable plate at Bridge front bulkhead and state if these bolts pass through the bulkhead plating as required by the regulations for Class A closing appliances.

It is concluded that three freeing ports are fitted on each side in the fore well and not six as stated on the report but the surveyor should conform this.



© 2020
S. Lloyd's Register
Foundation

004971-004981-0152