

# Lloyd's Register of Shipping.

Ship's Name *S.S. "MANCHESTER PROGRESS".*

Official No. 147432.

*Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in Manchester.*

- (1). The tonnage opening in shelter deck has now been restored and fitted with efficient temporary covers, and openings in tonnage well bulkheads are closed with the same type of closing appliances as originally viz: Stormboards in riveted channels.
- (2). Scupper pipes which were led to hold bilges have been permanently closed by welded plates and the shelter 'tween decks are drained by scupper pipes led to the machinery space bilges with lever weighted cocks at their lower ends.
- (3). The 5" overboard scuppers with screw down non-return valves controlled from shelter deck, fitted in tonnage well; the covers, supports, bearing surfaces, tarpaulins and battening arrangements of the second deck hatchways; and the means of closing of the openings in the machinery casings in the shelter 'tween decks, are all now in order.



*Noted  
A.M.  
15-12-47*

