

DUPLICATE

The British Corporation Register of Shipping and Aircraft.

HEAD OFFICE:
10, WYTHSWOOD SQUARE,
GLASGOW.

Port of Bombay,

COLLISION DAMAGE REPORT NO: I/764.

Bombay, 12th February, 1949

Carrier "Gladys Moller."

The Undersigned

J. J. WALMSLEY,

Surveyor to this Corporation did at the request of Messrs.
Messrs. Finlay & Co., Ltd., attend the S.S. "Gladys Moller" of London,
Official No: 181799, Gross 10712 Tons, while the vessel lay in Hughes
-dock, Bombay, on the 8th February, 1949, and on subsequent dates in
order to examine and report upon damage stated to have been sustained in
sequence of collision with H.M. Tug "Assiduous" at Aden, about 1145 hours
on the 31st March, 1948. For further particulars see vessel's Log Book
also the Master's letter to the Officer Commanding H.M.S. "Assiduous"
at Aden, 31st March, 1948, and this report as follows :-

External damage:- Port Side Shell plate Strake "H" No. 3 from
forward set in over an area of about ten feet by two feet in way
of Deep transverse frame No. 81 and the 1st Longitudinal frame
below the dry cargo hold deck level.

Internal damage :- Deep Transverse Frame No: 81 slightly
buckled on the upper part of its web plate between the dry cargo
hold deck stringer plate and the 1st Longitudinal frame below this
deck level.

Horizontal flat bar stiffener of the web plate of Deep Transverse
frame No. 81 slightly buckled over eight inches from the port wing.

1st Longitudinal Frame below the dry cargo hold deck very
slightly distorted in the vicinity of Transverse Frame No. 81.

Vertical Stiffener, immediately abaft Frame No. 81, and lying
between the dry cargo deck and the 1st Longitudinal Frame, very
slightly distorted. (Damage negligible).

(OVER)

© 2020
Lloyd's Register
Foundation

J.J.W.
005069-005074-0178

DUPLICATE

-- 2 --

(6) No trace of fracture on the Shell plate was observed and the undersigned Surveyor again examined the Shell Plate when the tank was full of water to the hatch coaming and no leak was noted.

(7) I agreed to the suggestion of the Owner's Engineer Superintendent that permanent repairs be carried out at the Owner's convenience, as I consider the vessel, so far as this incident is concerned, to be on this 11th day of February 1949, in a Seaworthy condition and fit to retain her Classification in this Corporation.

Mr. J. Rundle, Surveyor to Lloyd's Register of Shipping, inspected the damage on account of the Ministry of Transport.

(Two visits).

Fees :- Rs.100/-.
Expenses :- Rs. 10/-.
Total :- Rs.110/-.

J. J. Walmsley

SURVEYOR TO THE BRITISH REGISTER OF SHIPPING AND
BOMBAY, INDIA.



© 2020

Lloyd's Register
Foundation

Report

THE

No. in

S.S.

Owners

Engine

De

Cyl

Boilers

Main. N

Aux. M

Donkey

Main S

Propelle

Class M

C

L

v

s

p

G

o

Ge

Ge

cc

da

at Visi

of Vi

Rs.

ERY

enses

Re.