


 BEVIS MARKS HOUSE,
 LONDON, E.C.3
 27/3/30
 EQUIPMENT TO RULE

OIL TANKER 450'-0" B.P. x 61'-9" M. x 34'-0" M.

TO CLASS LLOYDS 100 A1, CARRYING PETROLEUM IN BULK.
SPECIAL NOTATION "LONGITUDINAL FRAMING AT BOTTOM AND AT DECK."

CURCHIN & WATSON,
BEVIS MARKS HOUSE,
BEVIS MARKS,
LONDON. E.C.3.

$$L/D = 13.24$$

THE SCANTLINGS ON THIS PLAN
EMBODY LLOYD'S REQUIREMENTS

8" x 3½" x .42 B.A. SPACED 31"

HATCH ON ONE SIDE OF DECK ONLY (NOT TO BE ARRANGED IN SAME TRANSVERSE PLANE AS HATCHES IN WING TANKS)

STIFFENERS 5" x 3 1/2" x .42 L
FITTED TO E. GIRDER,
TWO IN EACH SPACE
BETWEEN TRANSVERSE BEAMS
AND BETWEEN BEAMS & BULKHEADS.

GIRDER AT CENTRE LINE
66" x .40 WITH
FACE BAR 6" x 3 1/2" x .50 L

(GIRDER ATTACHED TO TRANSVERSE
BULKHEADS BY BRACKETS 7'-0"
LONG FROM TOE OF BRACKET
TO BULKHEAD.
SEE PLAN OF TRANSVERSE BULKHEAD.)

M

"Malvinia"

~~GEN. BOX NO 361~~

Yunwood 3200

~~Trans Rbls~~

Midship Section

see section as built.



© 2020

Lloyd's Register
Foundation

005075-005081-0060