


(Received at London Office

THURSDAY

Return saddle plate & gross neck was found to be
leaking. This was caulked, steam raised &
allowed to die off & the part again examined
& found satisfactory.
A few stay nuts on the lower back end plate were
noted to have been leaking slightly & were
rejointed, examined after steam had been raised &
found tight.
These defects would appear to have been caused
by raising steam too quickly.

N.B.—If this Report is copied by copying Press, especial care must be taken that the copying paper is not so much damped as to spread the ink, or to cause it to show through to the other side.

THE SURVEYORS ARE REQUESTED NOT TO WRITE ACROSS THE MARGIN.



© 2020
Lloyd's Register
Foundation