

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.

(COMPUTATION FOR STEAMER, SAILING SHIP, TANKER.)

DUTCH GOVERNMENT  
COPY WRITTEN

Index. No.

35754

(For London Office only).

"OCEANIC"

Ship's Name <b>NOORDAM</b>	Official Number -	Nationality and Port of Registry <b>Dutch</b> <del>Rottterdam</del> <b>PANAMA</b>	Gross Tonnage <b>10726</b>	Date of Build <b>1938</b>	Port of Survey <b>Rottterdam</b>
Moulded Dimensions: Length <b>145.137 m.</b> Breadth <b>19.507 m.</b> Depth <b>12.192 m.</b>				Date of Survey <b>28 July, 4th. Aug 1938</b>	
Moulded displacement at moulded draught = 85 per cent. of moulded depth <b>20380 m<sup>3</sup></b>				Surveyor's Signature <b>H. van der Wal.</b>	
Coefficient of fineness for use with Tables <b>.695</b>				Particulars of Classification <b>+100A1</b> (Continued)	

Depth for Freeboard (D).	Depth correction.	Round of Beam correction.
Moulded depth ... .. <b>12.192</b>	(a) Where D is greater than Table depth (D-Table depth) R = <b>8.33(12.230 - 9.677) × 30 = +638%</b>	Moulded Breadth (B) <b>19.507</b>
Stringer plate ... .. <b>10</b>	(b) Where D is less than Table depth (if allowed) (Table depth-D) R = -	Standard Round of Beam = $\frac{B \times 100}{50} =$ <b>390</b>
Sheathing on exposed deck $T \left( \frac{L-S}{L} \right) = 75 \times .3706 =$ <b>28</b>	If restricted by superstructures -	Ship's Round of Beam = <b>305</b>
Depth for Freeboard (D) = <b>12.230</b>		Difference <b>85</b>
		Restricted to Correction = $\frac{\text{Diff}}{4} \times \left( 1 - \frac{S_1}{L} \right) = \frac{85}{4} \times .3736 =$ <b>+8%</b>

## DEDUCTION FOR SUPERSTRUCTURES.

	Mean Covered Length (S)	Equivalent Enclosed Length (S <sub>1</sub> )	Height	Height Correction	Effective Length (E)
Poop enclosed <i>equivalent</i> ... ..	<b>11.006</b>	<b>11.006</b>	<b>2.438</b>	-	<b>11.006</b>
... overhang ... ..	<b>.026</b>	<b>.013</b>			<b>.013</b>
R.Q.D. enclosed ... ..					
... overhang ... ..					
Bridge enclosed ... ..	<b>65.364</b>	<b>65.364</b>	<b>2.667</b>	-	<b>65.364</b>
... overhang aft ... ..					
... overhang forward ... ..	<b>.838</b>	<b>.419</b>	<b>2.333 (virtual)</b>		<b>.419</b>
Fore enclosed ... ..	<b>14.111</b>	<b>14.111</b>	<b>2.286</b>		<b>14.111</b>
... overhang ... ..					
Trunk aft ... ..					
... forward ... ..					
Tonnage opening aft ... ..					
... forward ... ..					
Total ... ..	<b>91.345</b>	<b>90.913</b>			<b>90.913</b>

Standard Height of Superstructure **2290**" " R.Q.D. **✓**Deduction for complete superstructure **1067%**Percentage covered  $\frac{S}{L} =$  **62.94**" "  $\frac{S_1}{L} =$  **62.64**" "  $\frac{E}{L} =$  **62.64**Percentage from Table, Line A. **50.49**

(corrected for absence of forecastle (if required))

Percentage from Table, Line B. **✓**

(corrected for absence of forecastle (if required))

Interpolation for bridge less than .2L (if required) **✓**Deduction = **1067 × .5049 = -539%**

## SHEER CORRECTION.

Station	Standard Ordinate	S	M	Product	Actual Ordinate	Effective Ordinate	S	M	Product
A.P. ... ..	<b>1463</b>	<b>1</b>	<b>1463</b>	<b>1119</b>	<b>1119</b>	<b>1</b>	<b>1119</b>	<b>1</b>	<b>1119</b>
1/4 L from A.P. ... ..	<b>650</b>	<b>4</b>	<b>2600</b>	<b>543</b>	<b>543</b>	<b>4</b>	<b>2172</b>	<b>4</b>	<b>2172</b>
1/2 L " ... ..	<b>162</b>	<b>2</b>	<b>324</b>	<b>133</b>	<b>133</b>	<b>2</b>	<b>266</b>	<b>2</b>	<b>266</b>
Amidships ... ..	<b>-</b>	<b>4</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>4</b>	<b>-</b>	<b>4</b>	<b>-</b>
3/4 L from F.P. ... ..	<b>325</b>	<b>2</b>	<b>650</b>	<b>269</b>	<b>269</b>	<b>2</b>	<b>538</b>	<b>2</b>	<b>538</b>
1/4 L " ... ..	<b>1300</b>	<b>4</b>	<b>5200</b>	<b>1081</b>	<b>1081</b>	<b>4</b>	<b>4324</b>	<b>4</b>	<b>4324</b>
F.P. ... ..	<b>2926</b>	<b>1</b>	<b>2926</b>	<b>2438</b>	<b>2438</b>	<b>1</b>	<b>2438</b>	<b>1</b>	<b>2438</b>
Total ... ..			<b>13163</b>				<b>10857</b>		

Correction =  $\frac{\text{Difference between sums of products}}{18} \left( .75 - \frac{S}{2L} \right) = \frac{2306}{18} (.75 - .3147) =$  **+56%**If limited on account of midship superstructure. **✓**

If limited to maximum allowance of 1 1/2 ins. per 100 ft.

Deduction for Tropical Freeboard.	Deduction for Fresh Water.	TABULAR FREEBOARD corrected for Flush Deck (if required)
Addition for Winter and Winter North Atlantic Freeboard.	Displacement in salt water at summer load water line	Correction for coefficient $\frac{695 + .68}{1.36} = \frac{1.375}{1.36}$
Depth to Freeboard Deck = <b>12.202</b>	$\Delta =$	Depth Correction ... .. <b>638</b>
Summer freeboard = <b>2.910</b>	Tons per inch immersion at summer load water line	Deduction for superstructures ... .. <b>- 539</b>
Moulded draught (d) = <b>9.292</b>	T =	Sheer correction ... .. <b>56</b>
Deduction for Tropical freeboard and addition for Winter freeboard = $\frac{d}{4}$ inches =	Deduction = $\frac{\Delta}{40 T}$ inches =	Round of Beam correction ... .. <b>8</b>
Addition for Winter North Atlantic Freeboard (if required) =		Correction for Thickness of Deck amidships ... .. <b>- 28</b>
		Other corrections, scantlings, etc. <i>to compare</i> <b>330</b>
		<b>1032 567 + 465</b>
		Summer Freeboard = <b>2910</b>

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, **291 cm.**

16 SEP 1938

Tropical Fresh Water Line above Centre of Disc ... ..	<b>20 cm.</b>
Fresh Water Line " " ... ..	<b>20 cm.</b>
Tropical Line " " ... ..	<b>Nil.</b>
Winter Line below " " ... ..	<b>Nil.</b>
Winter North Atlantic Line " " ... ..	<b>✓</b>

Tropical Fresh Water Freeboard ... ..	<b>271</b>
Fresh Water " " ... ..	<b>271</b>
Tropical " " ... ..	<b>291</b>
Winter " " ... ..	<b>291</b>
Winter North Atlantic " " ... ..	<b>✓</b>

Lloyd's Register  
Foundation