

William Gray & Co., Limited, West Hartlepool.Yard No.1181.**F.E.**  
(FBD.)Similar to the "EMPIRE ALDGATE" etc.

TEMP

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME s.s."EMPIRE SOUTHWARK"REPORT Hpl. No. 18683

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

TELEPE

1st Long. No. 7722

Depth "d" 21.25 to U dk  
26.00 to Q dk

2nd Long. No. 22177

Proportions = L 12.61 to U dk  
D 10.55 to Q dk

Framing Bulb angle frames as approved

Sheerstrake As approved

The scantlings are suitable for a draught which is  $11\frac{1}{2}$ " less than that corresponding to the freeboard which could be assigned as a F.S. vessel.

The tank top plating has been increased in thickness in lieu of ceiling under the hatchways.

This vessel appears to have been built in accordance with the Rules and the approved plans, and it is submitted she is eligible to

be classed ~~LOCAL~~ "With freeboard"  
9.45 Hpl.

The Summer Freeboard as shown on the attached extract from the Freeboard Verification Form, now marked on the vessel's sides, to be inserted in the classification certificate and recorded in the Register Book, and further, the remaining freeboards, as shown on the accompanying extract, to be inserted in the certificate of classification.

1 Dk

Cell DB 266' 855t, MT 16' 603t, FPT 228t, APT 44t

FK, One Intermediate BH dispensed with, 4BH, pt.Cem., Lloyd's A &amp; CP

P 71' Q 202' F 29'

Trunk on U dk 83' on Q 126'

Mchy Aft

O.L. 328.0'

u

The Certificate of Classification to be endorsed "Cargo buttens not fitted" and the same notation to be printed in the Register Book.

The class is assigned and maintained upon the understanding that the equipment will be made to accord with the requirements of the Rules when the present state of emergency has passed.

Insert in/S.R.L:- (A bower anchor and 45 fathoms of chain cable to be supplied).

18.9.45.