

ived by Chief Ship Surveyor

Received from Chief Ship Surveyor

SSEL'S NAME *LtL S.S. "Saint Boniface"* Rpt. *Can* No. *83*.

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

ture of Survey

First Entry.

It is further submitted before this case receives the consideration of the Committee the Caen Surveyor should be requested to state:—

① Whether the width of the rudder post of stern frame is $212 \frac{m}{m}$ as amended on plan approved 15.2.21 or $210 \frac{m}{m}$ as reported ✓

② Whether the thickness of the brackets to hold transverses is $15.24 \frac{m}{m}$ as shown on the approved ✓ midship section and not as reported i.e. $10.67 \frac{m}{m}$ on F.E. and $10.16 \frac{m}{m}$ to $11.18 \frac{m}{m}$ by letter.)

(It is concluded the Surveyor has reported the thicknesses amidships and at ends of the brackets to shell longitudinals in view of the thicknesses of the "hold brackets" as reported agreeing therewith.) ✓

No copy of the shell expansion plan approved 1-8-21 can be found in this office, but on the plans of midship section and shell expansion approved 16/2/21, and shell expansion for longitudinals approved 25/2/21, Nos. 1 and 2 Longlo. are $228.6 \times 88.9 \times 15.24 \frac{m}{m}$ Ba and No. 3 $254 \times 88.9 \times 12.7 \frac{m}{m}$ Ba and not $230 \times 90 \times 11 \frac{m}{m}$ Ba. and $235 \times 90 \times 12.5 \frac{m}{m}$ Ba. as reported.

It is noted the diameters of the rudder main piece at head and heel are $343 \frac{m}{m}$ and $260 \frac{m}{m}$ respectively, and not $360 \frac{m}{m} \times 3/6 \frac{m}{m}$ and $270 \frac{m}{m} \times 223 \frac{m}{m}$ respectively in section as reported ✓

22/2/23

005180-005186-0108

Lloyd's Register Foundation
20/2/23.