

S.S. "SAINT BONIFACE"

Hav. Rpt. 4863.

It is submitted the Havre Surveyors be informed in reply to their cable of the 30th ult. that the diameter of the main boiler safety valves, viz:- 70 mm., do not comply with the Rules for ordinary valves for a working pressure of 15 kgs. per sq.cm. and they should be requested to state whether the boilers are fitted with full bore valves and whether the accumulation of the pressure did not exceed 10% of the loaded pressure under full firing conditions as required by the Rules.

Paul J. W.
1. 1. 23.



© 2020

Lloyd's Register
Foundation

005180-005186-0142