

GLASS CONTEMPLATED.

## (LLOYD'S REGISTER.)

## VESSELS OF 100 TONS AND UPWARDS.

G.R. 130.  
Lloyd's Register.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.  
Signal Letters (if any) G.Y.T.N.

Official Number.	Name of Ship.	No., Date, and Port of Registry.		
161,594.	Peebles.	6/1936. Newcastle.		
No., Date, and Port of Previous Registry (if any). First Registry.				
Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Motor Screw.	Sunderland.	1936.	William Doxford & Sons Ltd., Sunderland.
Number of Decks .. One & Shelter Deck		Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post .. .. .		Feet. Tents.
Number of Masts .. Two		Length at quarter of depth from top of weather deck at side amidships to bottom of keel .. .. .		423 6.0
Rigged .. .. . Schooner		Main breadth to outside of plank .. .. .		414 9.6
Stern .. .. . Conical		Depth in hold from tonnage deck to ceiling at midships .. .. .		54 2.5
Build .. .. . Clincher		Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards .. .. .		26 1.0
Galleries .. .. . None		Depth from top of beam amidships to top of keel .. .. .		29 7.9
Head .. .. . Straight		Depth from top of deck at side amidships to bottom of keel .. .. .		28 8.6
Framework and description of Steel Cargo vessel .. .. .		Round of beam .. .. .		1 1.2
Number of Bulkheads .. .. . Screw W.T.		Length of engine room, if any .. .. .		42 0.0
Number of water ballast tanks, and their capacity in tons .. 14-2587.				

## PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel } 10195 Tons. Ditto per inch immersion at same depth } 45.0 Tons.

## PARTICULARS OF PROPELLING ENGINES, &amp;c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set. Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B. H. P. I. H. P. Speed of Ship.
One	Internal Combustion Direct Acting Opposed Piston Type Vertical.	Engines. British	Engines. 1936.	Engines. Wm. Doxford & Sons Ltd., Sunderland	Three Upper Piston 880 M/M Lower Piston 520 M/M 1200 M/M		388 1800 2060
No. of Shafts.	Particulars of Boilers.	Boilers.	Boilers.	Boilers.			
One	Description Auxiliary Number 1 Horz: 1 Vert. Iron or Steel Steel Loaded Pressure 120 lbs.	British	1936.	Horz: Stockton Chem. Engrs. & Vert: Blair & Co. Annan, Ltd.	(20 1/2") Total 2080 M/M (82")		11 Knots.

## PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck .. .. .	4627.49	On account of space required for propelling power	1594.16
Space or spaces between Decks .. .. .		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	191.75
Turret or Trunk .. .. .	24.36	These spaces are the following, viz. :— Three deck houses & below aft. (Number of Seamen or Apprentices for whom accommodation is certified... 35.....)	
Forecastle .. .. .	97.66	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :—	
Bridge space .. .. .	183.84	Masters Accommodation 12.75)	
Poop or Break .. .. .	46.50	Chart Space 5.60)	
Side Houses .. .. .	1.90	Wireless Space 3.10)	127.45
Deck Houses .. .. .		Boatswains Stores 49.82)	
Chart House .. .. .		Water Ball Total Spaces 56.18)	1913.36
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 .. .. .	4981.75		
Excess of Hatchways .. .. .	14098.35		
Gross Tonnage .. .. .	5414.81		
Deductions, as per Contra .. .. .	3068.39		
Register Tonnage .. .. .			

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 604.24 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 114.19 tons.


NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Shelter 'Tween Decks Part I L. 367.2' - 1298.87 tons.

Shelter 'Tween Decks Part II L. 7.8' - 26.52 tons.

Open passageway in round house L. 52.9' - 12.55 tons.

Open passageway in round house L. 49.9' - 11.84 tons.



Name of Master	Certificate of	Service Competency	No.
Name, Residence, and Description of Managing Owner if there are more owners than one.			
B.J. Sutherland and Company Limited ) 38, Sandhill, Newcastle-upon-Tyne. ) Sixty-four shares. ) Sir Arthur Munro Sutherland, Baronet, K.B.E., of same address—Manager—.			

dated 30th April, 1936.

Wt. 11709/390. 2,000. 9/32. Wy.P.C. Gp. 613.

005187-005193-0329

Lloyd's Register  
Foundation