

LLOYD'S REGISTER OF SHIPPING

13 JUL 1955

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name "SWANSTREAM"

Official No. 161594

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

Access Openings.Upper Deck.

Access openings to Tween Decks 2 ft. x 2ft cut in Upper Deck inside line of openings in following positions, abaft No. 1 hatch, forward of No. 2 hatch, forward of No. 3 hatch, abaft No. 4 hatch, forward of No. 5 hatch.

Hatch coamings 24" high x .50 fitted at all openings provided with 3" wood covers, having 3" bearing surface.

Two tarpaulins supplied to each hatch.

Cleats, battening bars, wedges and locking bars provided as per Rules.

Compensation fitted for cutting openings in deck.

Second Deck.

Access openings to holds cut in second deck inside line of openings in following positions.

Abaft No. 1 hatch, forward of No. 2 hatch, forward of No. 2A hatch, abaft No. 4 hatch, forward of No. 5 hatch.


Hatch coamings 9" x 32" x .40 BA fitted at all openings, provided with 3" wood covers, having 3" bearing surface.

One tarpaulin supplied to each hatch.

Cleats, battening bars and wedges provided as per Rules.

Note: Above work, except for one hatch, not carried out at this Port but no Report available covering alterations.

K. J. Fitchett

Sydney N.S.W.
28 June 1955.Noted
am.
H.J.W.

© 2020

Lloyd's Register
Foundation

005187-005193-0337