

Lloyd's Register of Shipping.

Ship's Name "PEEBLES".

Official No. 161594.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Reassignment of Freeboards. (Reopening of Shelter deck).

Tonnage opening restored and closed by efficient temporary covers. ✓

Openings in tonnage well, forward bulkhead and tween deck bulkheads fitted with stormboards in riveted and welded channels. Scuppers ~~are~~ to hold bilges permanently closed. ✓

Shelter tween decks drained to machinery space bilges by 2 scuppers (P. & S.) fitted with self closing cocks. ✓

Drainage holes cut in wings of tween deck bulkheads. ✓

Overboard scupper 5" diameter fitted (P. & S.) in tonnage well with screwdown non-return valve controlled from shelter deck and fitted with indicator showing whether valve is open or shut. All hatchways on second deck are in accordance with Rules. ✓

Freeboards now measured from second deck. ✓

W. A. Robinson.

SURVEYOR TO LLOYD'S REGISTER.

Liverpool 9/11/16.

NOTE :- Part of above work carried out at some previous time.

Copy placed on board vessel

W. A. R.

ML-D.

Noted
JBD
11 OCT 16