

## Lloyd's Register of Shipping.

Ship's Name

PEEBLES.

Official No.

161594.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in (See also CONT<sup>d</sup> C.11. NWC. RPT. N<sup>o</sup> C.22609)

PARTIAL CONVERSION BACK TO ORIGINAL OPEN SHELTER DECK TYPE

The following items remain to be effected to complete the conversion.

- ① The Tonnage opening in the Shelter Dk to be restored and closed by efficient temporary covers. ✓
- ② An overboard scupper not less than 5" dia to be fitted on each side of Tonnage well with a screw down automatic non return valve controlled from the shelter deck having an indicator showing whether valve is open or shut, or freeing ports and overboard scuppers being restored on each side of the Tonnage well. ✓
- ③ All hatchways on the second deck having coamings, covers, supports, heaving surfaces, tarpaulins, cleats and battening arrangements in accordance with the Rules. ✓

Newcastle

G. Young

23.5.46.

A copy of the above has been sent to the Owners.