

Lloyd's Register of Shipping.

Ship's Name

Tug "GUARDSMAN" ex "EMPIRE NINA".

Official No. 180474.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in HULL.

1. Flush bunker scuttles to galley P. & S. on upper deck removed, replaced by oil tight hatches 18" x 15" x 24" high, coaming .375". Fitted with hinged oil tight covers, secured by screwed toggles.
2. Fiddley hatch fitted on casing aft of funnel 3'6" x 20" x 10" high, with hinged steel cover 1/4" thick.
3. Access hatch fitted on forward side of funnel S.S. 2'0" x 2'0" x 10" high, with hinged steel cover 1/6" thick, secured by screws and toggles.

MLD

J. Dobbie.

SURVEYOR TO LLOYD'S REGISTER
OF SHIPPING.

17th July, 1947.

Lb. 2797
26-7-47

