

Lloyd's Register of Shipping.

Ship's Name "ROYAL DAFFODIL"

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

ALTERATIONS

NOW DONE:- New hatchway 7' 6" x 7' 6" fitted on Sun Deck aft, enclosed by strongly constructed wood trunk, carried down to main deck to mail and baggage room.

Corners of trunked hatch suitably stiffened, and additional supports fitted under floor of mail room.

Hatchway on sun deck coaming 30" high, fitted with 7" B.A. fore and after, hatch cleats, and 2 tarpaulins supplied.

Shell gangway doors on port and starboard sides 2(p.s.) and 2(s.s.) closed by E.W. on completion doors hose tested and found satisfactory.

NOTE:- It was noted at this time that B.O.T. have given the vessel 6" more draught, The new Freeboard is now 3' 11" and new draught 9' 3".

Extract from Glasgow Rpt 67602
Dated 25 Sept 43

SZ.B. 5 Oct 43.

