

CLASS: ENGLISH LLOYD ✕ 100 A.1

LENGTH P.P. 54.3 m = 178'-2 1/4" E.C.

BREADTH MOULDED 9.30 = 30'-6 1/8"

DEPTH MOULDED - - - - - 4,575 - 15' - 0" . .

TRANSVERSE N° B.D. ———— 45.51

LONGITUDINAL N° LN = — — — — 8108.

PROPORTION L/D TO UPPER D'K --- 11.88

ANCHORS (STOCKLESS) - - - 2-26-2-14, 1-14 1/2 CWTs

STREAM ANCHOR, STOCK INCLUDING ----- 1-6 1/2 "

KEDGE      "      "      "      -----  $1 + 3\frac{1}{2}$  "

STUD CHAIN CABLE. DIA. OF IRON. -----  $1\frac{5}{16}$ "

TOTAL LENGTH. — — — — — 210 FATHOMS

75 FATHOMS STEEL WIRE ----- 3 1/4"

120 - 4" MANILLA.

BUTTS OF FLAT PLATE KEEL.		AT ENDS	
" "	GARBOARD STRAKE	3 R LAP	2 R LAP
" "	SHEER STRAKE	3 R LAP	2 R LAP
" "	BOTTOM, BILGE STRAKE BELOW		
" "	SHEER STRAKE AND SIDE PLATING.	2 R LAP.	2 R LAP.
" "	CENTRE GIRDER AND MARGIN PLATE	2 R LAP.	
" "	DOUBLE BOTTOM CENTER STRAKE	2 R LAP.	
" "	" " " " TOP PLATING.	2 R LAP.	1 R LAP.
" "	DECK STRINGER.	3 R LAP.	
" "	DECK PLATING	2 R LAP.	1 R LAP.
LANDINGS OF ALL SHELL PLATING EXCEPT STRAKES J & K.		2 R LAP.	
" "	STRAKES J & K.	1 R LAP.	
" "	DECK PLATING	1 R LAP.	
" "	DOUBLE BOTTOM TOP PLATING.	1 R LAP.	

S.S. WATERWAY.


PART. No. 14. 5		Base No.	
MIDSHIP SECTION.		SHALP	173
		1:25.	UTLAG.
			PLATSLAG.
			FRG.
			TRAM V.
HIT. AV.			SKERK V.
KOP. AV.			SK. K. V.
			SKIDES.
			KOPSL.
Linnhems Skeppsvärk Antiklog			
DATE		20-10-20	
LR		Hovd's Register	
		9F. 847.	

005280. 005292. 0172



S.S. Waterway.  
Lindhannus Skoppsbarr's Yard No. 14.  
Midship section.  
Vessel as built.

Malinö F.E. Report No. 325.



© 2021

Lloyd's Register  
Foundation

005280-005292-0172