

12 JAN 1966

SHIP'S NAME "W.D. ATLAS"

PORT WYA

No. 840

LAST SURVEY DATE 20.7.65.

CLASS IS SUBJECT TO NIL

Repairs.

Steering-gear found to be defective. The dredger is stated to be dredging at Whyalla without the use of the steering-gear - the surveyor recommends that the steering-machinery holding-down bolts be hardened up or renewed as necessary, all steering-machinery hydraulic pressure pipes be annealed and tested, steering machinery relief-valves be overhauled and adjusted and extension shaft between steering machinery and upper deck being checked for possible twist before the ship leaves Whyalla.

G.S. Advanced.

S.R.L. - Appendix Note
non.

It is recommended that this
remain
as CLASSED, subject as now recommended.

12/1/66.

NB SPS due 3/65.
MBS. due 9/65.



© 2020

Lloyd's Register
Foundation

005293-005300-0157