

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office

24 DEC 1924

Date of writing Report 9.12.1924 When handed in at Local Office 22.12.24 Port of GLASGOW.

No. in Survey held at GLASGOW. Date, First Survey 27.10.24 Last Survey 12.12.1924
Reg. Book.

(Number of Visits 5)

89/43. on the S.S. HISTORIAN.

Tons { Gross 5074
Net 3450

Built at GLASGOW. By whom built C. CONNELL & CO Yard No. 400 When built 1924

Owners CHARENTE S.S. CO (T. & J. HARRISON). Port belonging to LIVERPOOL.

Electric Light Installation fitted by MESSRS H.T. ROBERTSON & CO Contract No. 400 When fitted 1924

System of Distribution

Single Wire

Pressure of supply for Lighting 100 volts, Heating — volts, Power — volts.

Direct or Alternating Current, Lighting Direct Power —

If alternating current system, state frequency of periods per second —

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes

Generators, do they comply with the requirements regarding overload Yes, are they compound wound Yes

are they over compounded 5 per cent. Yes, if not compound wound state distance between each generator —

Where more than one generator is fitted are they arranged to run in parallel —, is an adjustable regulating resistance fitted in

series with each shunt field Yes

Are all terminals accessible and clearly marked Yes, are they so spaced or shielded that they cannot be accidentally earthed,

or short circuited Yes Are the lubricating arrangements of the generators as per Rule Yes

Position of Generators Above Eng Room Store Starboard side

is the ventilation in way of the generators satisfactory Yes, are they clear of all inflammable material Yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators

— and —, are the generators protected from mechanical injury and damage from water, steam or oil Yes

are their axis of rotation fore and aft Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes are the prime movers and

their respective generators in metallic contact Yes

Main Switch Boards, where placed Above Eng Room Store

If the generators and main switchboard are not placed in the same compartment, is each generator provided with

a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard —

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes

are they protected from mechanical injury and damage from water, steam or oil Yes, if situated near unprotected

woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards — and —

are they constructed wholly of durable, incombustible non-absorbent materials Yes, is all insulation of high dielectric strength and of

permanently high insulation resistance Yes, if semi-insulating material is used, are all conducting parts connected to one pole

insulated from the slab with mica or micanite and the slab similarly insulated from its framework Yes, and is the

frame effectively earthed Yes Are the following fittings as per Rule, viz.: — spacing or shielding of live parts

Yes, accessibility of all parts Yes, absence of fuses on back of board Yes, proportion of omnibus

bars Yes, individual fuses to voltmeter, pilot or earth lamp Yes, connections of switches Yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

S.P. main Switch & S.P. main Fuse
S.P. circuit " & " Fuses to each outgoing circuit

Instruments on main switchboard 1 ammeter 1 voltmeter — synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules Yes

Section and Distribution Boards, is the construction, protection, insulation, material, and position of these, as per rule Yes



© 2021

Lloyd's Register
Foundation

005307-005310-0147

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office.....

[illegible]

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
The foregoing is a correct description.

H. T. Robertson & Co.

Electrical Engineers.

Date *13th Dec^r 24*

COMPASSES.

Distance between electric generators or motors and standard compass

100 ft

Distance between electric generators or motors and steering compass

100 ft

The nearest cables to the compasses are as follows:—

A cable carrying *8* Amperes *12* feet from standard compass *10* feet from steering compass.

A cable carrying *2* Amperes *into* feet from standard compass *into* feet from steering compass.

A cable carrying Amperes feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power *yes*.

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *yes*.

The maximum deviation due to electric currents was found to be *7 1/2* degrees on *every* course in the case of the standard compass, and *7 1/2* degrees on *every* course in the case of the steering compass.

For CHARLES CONNELL & CO., Limited.

N. McCallum

SECRETARY. Builder's Signature.

Date

17 Dec 1924

Is this installation a duplicate of a previous case *no*. If so, state name of vessel

General Remarks (State quality of workmanship, opinions as to class, &c.)

This installation has

*been fitted on board under special survey.
Tested under full working conditions
and found satisfactory. The workmanship
was found to be good and sound.*

It is submitted that
this vessel is eligible for
THE RECORD. Elec. light.

W.D.
31/10/24

Total Capacity of Generators *12.5* Kilowatts

The amount of Fee ... £ *12. 10. 0* When applied for, *20/12/24*

Travelling Expenses (if any) £ : : *See debit book.* When received,

J. S. Rankin.
Surveyor to Lloyd's Register of Shipping.

Committee's Minute *GLASGOW 23 DEC 1924*

Assigned *Elec. Light.*



© 2021

Lloyd's Register
Foundation

Im. 22. Transfer.
(The Surveyors are requested not to write on or below the space for Committee's Minute.)

A. G.
22/12/24.