

"LARISTON" - No.78121 in the Register Book

A telephone message was received from the Glasgow Surveyors who stated that the owners desired to fit a Marconi crystal type echometer, type F4, TER projector, in the after cofferdam between the cargo tanks and oil fuel bunkers.

They were informed that this could be done, provided the following requirements of the Committee were complied with:-

1. Fitting is to be in accordance with standard ^{approved} plan.
2. Electrical connections are to be in accordance with the ~~Rules for carrying Petroleum in Bulk.~~ *Section 15 of the Rules for Electrical Equipment*
3. Cables in the cofferdam are to be enclosed in heavy gauge screwed gas-tight tubing ~~and~~ the converter boxes are to be of ^{approved} gas-tight pattern.
4. The fittings are to be of flame-proof construction.

It is submitted a confirmation of this be sent to the Glasgow Surveyors.

Lt. Ls. 5-8-40

J.M.M.
W.L.
5th August, 1940.
Cow.



© 2021

Lloyd's Register
Foundation

005311-005317-0018