


COPY

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

14 AUG 1953



Halifax, N. S.,

Port

E.S.S. "IMPERIAL WINNIPEG"

Disaster of Unknown Date

This is to Certify that

J. STEVENSON

the undersigned Surveyor to this Society did at the request of

the Owners, attend the Steel Single Screw Turbo-electric Steamship "IMPERIAL WINNIPEG", 10,700 tons gross register, of Montreal, Quebec, on 22nd June, 1953 and subsequent dates whilst she lay on the blocks in the Floating Dock at Halifax Shipyards, Ltd., Halifax, N. S., after damage to port side shellplating stated to have been sustained by striking an unknown object on an unknown date.

Upon examination, the Undersigned:

FOUND

SHELLPLATING

Port Side (Numbered from Forward)

"G" Strake, Plate No. 6 deeply set in.

"H" Strake, Plate No. 6 deeply set in.

FRAMES (Numbered from Deck)

Longitudinal frames Nos. 4, 5 & 6,
buckled.

All new and disturbed work to be coated.

Upon completion of repairs, No. 2 cargo oil tank, port side, is to be tested with a head of water to the top of the hatch coaming, and proved tight.

These recommendations have been made with a view to the vessel being restored, as far as practicable, to the same condition as before the alleged casualty occurred.

All recommended repairs and tests have been completed, at this time, to my satisfaction.

RECOMMENDED

To be cropped and part renewed.

To be cropped and part renewed.
Adjacent seams and butts to
be faired in place.

To be cropped and part renewed.

J. Stevenson
Surveyor to Lloyd's Register

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that :—

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."