

## Lloyd's Register of Shipping.

F. 894 (SNG.)Ship's Name "STANVAE MANILA"Official No. 172803

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
 in since building

A fabricated steel plate access hatchway with strongly constructed hinged water  
 tight steel cover now fitted at port side of the centre castle deck. An  
 electrically welded doubling plate fitted in way of the deck opening.

Description of hatchway:- Diameter of hatchway 18 inches internal; Height of  
 coaming 24 inches; Thickness of coaming plate 0.4 inches; Thickness of cover  
 plate 0.5 inches; cover capable of being manipulated from both sides. ✓

W.P. Watson

5<sup>th</sup> July, 1952

JL

24 SEP 52