

9-AUG 1955

Rpt. C. 11 (Contd.)

Index No.

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name 'BRITISH CROWN'

Official No. 184648

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in


Sanitary discharges from Bridge Space previously led overboard above
upper deck now carried down through wing tanks in way and led through ship's
side. Non return valve fitted above deck. On port side - No 5 tank - 2 m.s. pipes
5" & 4" dia x 3/4" thick and on starboard - No 5 tank - 2 m.s. pipes 5" dia x 3/4" thick
and starboard - No 6 tank - 2 m.s. pipes 4" dia x 3/4" thick welded 11m0' deck
and shell anchoring 9'0" below deck & above load line.

J MacLeod
Surveyor to Lloyd's Register
Newcastle 4th Aug. 1955

Noted

JMB
17-8-55

(Copy Made on Board)



© 2020

Lloyd's Register
Foundation

005337 - 005343 - 0084