

40274  
18 SEP. 1952

Rpt. C. 11 (Contd.)

Index No. ....

## LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name BRITKON B.C. CLASS Official No. 160233

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in .....

The vessel has at this time been converted for oil burning, with the cross bunker space converted to carry oil fuel, in accordance with plan approved 17/6/52. Side hatches (1 port, 1 star'd) on Bridge Deck have been reduced in size from 18'-8" x 5'-0" to 5'-0" x 5'-0" by plating over the unnecessary openings and fitting deck beams in way, the after coamings being moved forward.

These hatches have been provided with hatch covers, tarpaulins, battens and cleats in accordance with Rule requirements.

Existing hatches in way on the 2nd. Deck (2 port, 2 star'd) each 4'-8" x 3'-3", have been fitted with hinged steel plate covers secured by toggles.

S. W. Gresham for R. Lyle.



A copy of the above has been placed on board the vessel.

16.  
19 SEP 1952



© 2020

Lloyd's Register  
Foundation

005344-005352-0217