

Lloyd's Register of Shipping.

Ship's Name "Port Chalmers"

Official No. 163429

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The tonnage opening on the shelter deck has been permanently closed by the fitting of a 6" x 3" bulb angle beam and wood decking, efficiently secured, caulked and payed.

The wash ports in the tonnage space permanently closed by the welding of steel plates over the openings. All the overboard scuppers from shelter tween decks closed by the fitting of of spigot plate patches over the openings in the shell plating, riveted in place and afterwards welded. Efficient arrangements have been provided for the tween decks to be drained to the bilges. The existing battening arrangements of the shelter tween deck hatchways have been maintained in efficient condition. Lifelines have been provided.

J. Brooke Smith.

10 January 1940

Noted *[Signature]*

11 JAN 1940