

# Lloyd's Register of Shipping.

Ship's Name "PRONTO"

Official No. 6278

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in JANUARY, 1933.

A new bulkhead has been erected at frame 109 extending to shelter deck and two new tween deck bulkheads at frames 47 & 78. Horizontal stiffeners fitted on present lower bulkheads at frames 47 & 78, all as per plan enclosed.

Two 3" bilge suction, one port and one starboard, fitted in the new No. 1 hold and all work tested on completion.

One companionway on shelter deck at after end of midship side house starboard side, leading to tween decks, enclosed by steel deck house, door of steel, can be operated from both sides, sill 18" (previously a coal hatch)

One companionway on shelter deck at aft end of bridge house and enclosed by steel bridge house, door of steel can be operated from both sides, sill 18" high (previously a cabin).

Two ventilators to forward tween decks 19" diam. x 8/20" x 5'6" high (supported from bridge front).

One ventilator to after tween decks 19" dia. x 8/20" x 10'9" high (supported from aft boat deck beam).

Deck doubled in way, wood plugs and canvas covers supplied.

(H.Kg. Rpt. 8 No. 7798 7.4.37.)

WHL  
26.5.37



© 2021

Lloyd's Register  
Foundation