

13 JUL 1946

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name "EMPIRE STOUR".

Official No. 162474.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The following alterations have now been carried out at Cardiff:-

The gunners' accommodation has been removed from the after end of the bridge space, port side.

The companionway on Bridge Deck, starboard side of mainmast, has been removed, and the opening in deck permanently blanked.

All side scuttles and lavatories in the bridge space have been removed and the holes in sides permanently closed with spigot patches.

The hinged watertight door fitted to the opening on port side of the bridge after bulkhead has been removed, and the opening has now been restored to its former size, 4'-6" x 3'-0", and fitted with stormboards in riveted channels, also with portable steel plate with hook bolts 15" apart.

The two hinged steel doors in the bridge forward bulkhead have been replaced by portable steel plates secured by closely-spaced through bolts.

E. Brimblecombe.

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.

10th July, 1946.

*Noted
JBD*
15 JUL 1946

© 2020

Lloyd's Register
Foundation