

COPY.

Lloyd's Register of Shipping.

Port

of Düsseldorf.

21st December 1928.

This is to Certify that

Victor Sárowak and Josef Loogen
the undersigned Surveyor to this Society did at the request of

Messrs. Press- & Walzwerk A.G. of Düsseldorf-Reisholz test and inspect on
the 19th December 1928 at their work the undermentioned seamless Siemens-
Martin Steel air receivers, ordered by Messrs. William Denny & Brothers Ltd.
of Dumbarton.

Specification.

No. of rec.	Outs. diam.	Thickness of shell	Length of receivers
11	590 mm	25 mm	3800 mm
1	330 mm	15 mm	2320 mm

Results of tests.

Sample No.	Tensile ten. in kg.p.sq.mm.	Elongation in 8"
13	47,7	24,5%
14	47,4	25,0%
15	49,6	23,5%
16	45,4	24,0%
17	48,0	23,0%
18	46,1	23,5%
19	46,3	25,5%
20	46,5	26,5%
21	45,8	25,0%
22	46,5	24,5%
23	46,3	26,0%
24	45,8	26,0%

Band tests good.

The receivers have not been tested by hydraulic pressure.

Identification marks: LLOYDS J.L. No. 604-609 28.9.28.
LLOYDS V.S. No. 1100-1105 19.12.28.

Surveyor to Lloyd's Register

Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any error or omission in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents of the Society.

Tested to 2000 lbs.