

SUPPLEMENTARY REPORT

Report on Vessel in respect to SPECIAL SURVEY No. 3, the part having been carried out while Damage Repairs were being made.

The bottom and side plating found in good condition and not well coated.

Bottom pintle found slack also had fit in rudder snug. Snug bored out true, pintle built-up, machined and fitted; made and fitted, wing spanner made for nut which was hardened and stopped. New ligum vitae bush fitted for bottom pintle.

A. HAYZEL. Cables were ranged P. & S., anchor shackle pins turned end for end. Lower half division plate on locker renewed; locker soaked out and recoated, steel and wood replaced or renewed as required.

Side and bottom plating well scraped, raw places primed, two coats of No. 1 paint applied and before leaving back one coat of No. 2 applied.

The greater part of the Special Survey No. 3 was carried out during drill test of hull plates, and completed with the examination of Nos 3, 4 & 5 Lower Holds and Double Bottom Tanks and Ward Riggings. Main rigging renewed with the exception of the fore and aft preventer stays. It has been recommended that the fore rigging be renewed before October 1944.

Generally the vessel was found in good condition and was well recoated as found necessary. Steering gear and windlass satisfactory.

Load Line General Survey was carried out and the necessary repairs and repairs in way of the damage in connection with this have been completed.

M. Propeller examined, also stern bush (external examination), sections and ship's side valves. The Main Engine injection pump casting softened; a new casting made, machined and fitted.

While the vessel was being repaired, advantage was taken to carry out the greater part of the LHC(99) Survey of the Main Engines. The No. 3, 4 & 6 Units were completely examined from cover to shaft, bearings & journals and part of the No. 5 Unit. Necessary repairs and repairs as recommended were carried out. Sea trials of Machinery one hour at half speed; trials satisfactory.

L. Liatt
SURVEYOR TO LLOYD'S REGISTER,
WELLINGTON, N.Z.



© 2021

Lloyd's Register
Foundation

005397-005402-0090