

REPORT ON ELECTRIC LIGHTING INSTALLATION. No. 8711.

Port of Bunda Date of First Survey 15:12:1922 Date of Last Survey 2:1:1923 No. of Visits 4
 No. in Reg. Book on the ~~Iron~~ Steel "Asiatic" "Arthurian" Port belonging to Hull
 Built at Burton Island By whom Burton Island S.B.Co. Ltd When built 1923
 Owners W. H. Cochrane & Co Owners' Address Hull
 Yard No. 112 Electric Light Installation fitted by Miss Moncrieff Arthur When fitted 1923

DESCRIPTION OF DYNAMO, ENGINE, ETC.

Vertical, Robey Engine, 5 1/2 x 5" single cylinder, forced lubrication, 8 kW. G.E.C. Dynamo, on common bedplate.

Capacity of Dynamo 80 Amperes at 100 Volts, whether continuous or alternating current continuous

Where is Dynamo fixed Engine Room Whether single or double wire system is used Double

Position of Main Switch Board Engine Room having switches to groups 5 of lights, &c., as below

Positions of auxiliary switch boards and numbers of switches on each No Auxiliary switch boards.

If fuses are fitted on main switch board to the cables of main circuit yes and on each auxiliary switch board to the cables of auxiliary circuits yes and at each position where a cable is branched or reduced in size yes and to each lamp circuit yes

If vessel is wired on the double wire system are fuses fitted to both flow and return wires or cables of all circuits including lamp circuits yes

Are the fuses of non-oxidizable metal yes and constructed to fuse at an excess of 25% per cent over the normal current

Are all fuses fitted in easily accessible positions yes Are the fuses of standard dimensions yes If wire fuses are used are permanent instructions fitted on or near each switch board giving particulars of proper size of fuse for each circuit yes

Are all switches and fuses constructed of incombustible materials and fitted on incombustible bases yes

Total number of lights provided for 95 arranged in the following groups:—

A	32	lights each of	40 W.	32	candle power requiring a total current of	13	Amperes
B	15	lights each of	60 W.	32	candle power requiring a total current of	6	Amperes
C	9	lights each of	32	32	candle power requiring a total current of	9	Amperes
D	20	lights each of	40 W.	32	candle power requiring a total current of	8	Amperes
E	19	lights each of	40 W.	32	candle power requiring a total current of	8	Amperes
2	Mast head light with	1	lamps each of	32	candle power requiring a total current of	2	Amperes
2	Side light with	1	lamps each of	32	candle power requiring a total current of	2	Amperes
5	Cargo lights of	96			candle power, whether incandescent or arc lights		Incandescent

If arc lights, what protection is provided against fire, sparks, &c. —

Where are the switches controlling the masthead and side lights placed Chart House

DESCRIPTION OF CABLES.

Main cable carrying	80	Amperes, comprised of	19	wires, each	15	S.W.G. diameter, .07650	square inches total sectional area
Branch cables carrying	20	Amperes, comprised of	7	wires, each	20	S.W.G. diameter, .007052	square inches total sectional area
Branch cables carrying	16	Amperes, comprised of	7	wires, each	22	S.W.G. diameter, .004266	square inches total sectional area
Leads to lamps carrying	7	Amperes, comprised of	3	wires, each	22	S.W.G. diameter, .001825	square inches total sectional area
Cargo light cables carrying	6	Amperes, comprised of	3	wires, each	22	S.W.G. diameter, .001825	square inches total sectional area

DESCRIPTION OF INSULATION, PROTECTION, ETC.


Vulcanised India rubber taped & braided gut served lead sheathed, taped, galvanized wire armoured then braided & compounded.

Joints in cables, how made, insulated, and protected Looped into porcelain extensions mounted on hard wood blocks then covered with b.f. cover.

Are all the joints of cables thoroughly soldered, and the flux used not containing acids or other corrosive substances yes Are all joints in accessible positions, none being made in bunkers, cargo spaces, or spaces which may at any time be used for carrying cargo, stores, or baggage yes

Are there any joints in or branches from the cable leading from dynamo to main switch board No

How are the cables led through the ship, and how protected Armoured & lead covered, slipped with galvanized iron clips.



005429-005475-0069

DESCRIPTION OF INSULATION, PROTECTION, ETC.—continued.

Are they in places always accessible *Yes*

What special protection has been provided for the cables in open alleyways or where exposed to weather or moisture *Lead covered*

What special protection has been provided for the cables near galleys or oil lamps or other sources of heat *Armoured*

What special protection has been provided for the cables near boiler casings *Armoured*

What special protection has been provided for the cables in engine room *Armoured & lead covered*

How are cables carried through beams *Armoured or bushed* through bulkheads, &c. *Bulkhead glands* ✓

How are cables carried through decks *Deck tubes* ✓

Are any cables run through coal bunkers *No* or cargo spaces *Yes* or spaces which may be used for carrying cargo, stores, or baggage *Yes*

If so, how are they protected *Armoured*

Are any lamps fitted in coal bunkers or spaces which may at times be used for cargo, coals, or baggage *No*

If so, how are the lamp fittings and cable terminals specially protected *—*

Where are the main switches and fuses for these lights fitted *—*

If in the spaces, how are they specially protected *—*

Are any switches or fuses fitted in bunkers *No.*

Cargo light cables, whether portable or permanently fixed *Portable* How fixed *in watertight connections*

In vessels fitted on the single wire system, how is the dynamo terminal fixed to the hull of vessel *—*

How are the returns from the lamps connected to the hull *—*

Are all the joints with the hull in accessible positions *—*

Is the installation supplied with a voltmeter *Yes*, and with an amperemeter *Yes*, fixed *Switchboard*

VESSELS BUILT FOR CARRYING PETROLEUM.

In vessels built for carrying petroleum, are all switches and fuses fitted in positions not liable to the accumulation of petroleum vapour or gas ✓

Are any switches, fuses, or joints of cables fitted in the pump room or companion ✓

How are the lamps specially protected in places liable to the accumulation of vapour or gas ✓

The copper used is guaranteed to have a conductivity of not less than that of the Engineering Standards Committee's standard, and the wires are protected by tinning from the sulphur compounds present in the insulating material.

Insulation of cables is guaranteed to have a resistance of not less than 600 megohms per statute mile at 60° Fahrenheit after 24 hours' immersion in water, the test being made after one minute's electrification at not less than 500 volts and while the cable is still immersed.

The foregoing statements are a correct description of the Electric Light installation fitted by us on this vessel and we declare that it is at this date in good order and safe working condition.

Wm. M. Crawford, B.Sc. Mitchell & Partners Ltd. Electrical Engineers Date *15 June 1923*

COMPASSES.

Distance between dynamo or electric motors and standard compass *158 ft.*

Distance between dynamo or electric motors and steering compass *163 ft.*

The nearest cables to the compasses are as follows:—

A cable carrying	1	Amperes	2	feet from standard compass	7	feet from steering compass
A cable carrying	1	Amperes	2	feet from standard compass	7	feet from steering compass
A cable carrying		Amperes		feet from standard compass		feet from steering compass

Have the compasses been adjusted with and without the electric installation at work at full power

The maximum deviation due to electric currents, etc., was found to be *Nil* degrees on *any* course in the case of the standard compass and *Nil* degrees on *any* course in the case of the steering compass.

THE BURNISLAND SHIPBUILDING COMPANY LTD.

Builder's Signature. Date

GENERAL REMARKS.

W. J. Day
This installation has been fitted on board in an efficient manner, and in accordance with the Rules: the materials and workmanship are sound & good. It has been tried under working conditions found satisfactory.

L.P.S-0-0.

It is submitted that this vessel is eligible for THE RECORD.

Elec. light.

J. Bell
J.W.D. 27/1/23

Surveyor to Lloyd's Register of Shipping.

Committee's Minute

THE SURVEYORS ARE REQUESTED NOT TO WRITE ACROSS THIS MARGIN.

