

13 DEC 1954

## Lloyd's Register of Shipping.

Ship's Name

Modesta "

Official No. 1290

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in July 1948 (Please see also Gen. Rpt. C. 11 (Contd.) from 23rd October 1952)

The existing openings in Bridge forward bulkhead are: 2 off 920 x 1225 mm with 500 mm fill and closed with steelhinged doors with 8 turnbuckles. ✓

Timber freeboard: Strong angle sockets riveted to stringer plates less than 6' from bulkheads and about 10' spaced, dimensions about 8½" in both directions. Uprights secured on top with 1" clamps fitted to bulwark rail. Sufficient lashing arrangements with ¾" close link chains supplied.

Sifelines fitted. Steering arrangement effectively protected and hand steering fitted. ✓

1" Eye plates fitted to sheerstrake, spaced less than 6' from end bulkheads and about 10' apart. ✓

Double bottom tanks Nos 2, 3, 4 & 5 now divided at C/L. ✓

V. J. J. J.

h.c.

13 DEC 1954



© 2020

Lloyd's Register  
Foundation