

Lloyd's Register of Shipping.

Ship's Name *MIRALDA*Official No. *162134*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in ✓

A steel watertight bulkhead has been constructed from side to side of vessel in the forecabin on the 7th frame from forward.

The plating is .38" thick & stiffeners are 5" x 3" x .40" (ordinary angles) spaced 33", bracketed to deck at bottom. Tops of stiffeners are riveted to boundary angle (no lug attachments)

There are no openings in the bulkhead.

A. Hunter

Robert Ross

21 NOV 1939



© 2020

Lloyd's Register
Foundation