

Lloyd's Register of Shipping.

Ship's Name *MIRALDA*Official No. *162134*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in *✓*

A steel watertight bulkhead has been constructed from side to side of vessel in the forecabin on the 7th frame from forward.

The plating is 38" thick & stiffeners are 5" x 3" x 40" (ordinary angle) spaced 38", bracketed to deck at bottom. Tops of stiffeners are riveted to boundary angle (no lug attachment)

There are no openings in the bulkhead.

*A. Hunter**Noted for*

1 NOV 1939



© 2020

Lloyd's Register
Foundation