

28118
6-SEP 1954

Rpt. C. 11 (Contd.)

Index No. 12104

Lloyd's Register of Shipping.

Ship's Name "TEFKROS" Official No. 140654

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

11
(ss) Small domestic coal bunker has been constructed. (ss) Tween deck and an all welded access hatch arranged on upper deck particulars as follows:-
Deck opening with well rounded corners. 18" X 18" and with 18" high coaming, extending below deck level between Fr. Nos.76 & 77 & extending 9" into deck stringer & next adjacent deck plate. Suitable deck compensating doubler 3'-10" X 18" X 3/8" fitted. Hinged 3/8" steel W/T cover complete with 4 screwed toggles supplied. All efficiently installed & hose tested.

A. G. Sinclair
Surveyor to Lloyd's Register,
Hong Kong.
19th July, 1954.

Noted
A.R.
13.9.54