

COPY.

# Lloyd's Register of Shipping.

No. 1867.

Port of BATAVIA. JAVA. N. E. I.

26th December, 1941.



10041  
Ce h

This is to Certify that

I, W. A. ROBERTSON,  
the undersigned Surveyor to this Society did at the request of

Messrs. N. V. Stoomvaart Maatschappij "Nederland" of Batavia,  
hold a survey on board of the Dutch Steamer:

"SINOKEP"  
6607 tons gross of Batavia, No. 83454 in Lloyd's Register Book  
1940/41, on the 22nd day of December 1941, in order to examine  
the Sanitary Outlet Valve situate Starboard side in after end  
of Lower Tween Decks Hatch No. 5, and report as follows:

I found the Casting had already been welded and was again  
cracked. Hammer tests showed that the metal was very thin and  
further crackage could be expected.

I ordered the Valve off and when examined it was too thin  
to weld so a full coverage patch was welded on in accord with  
my instructions.

A new spare Valve is recommended as present Valve cannot  
be relied upon for more than a year.

The work being completed to my satisfaction I have reported  
so to Lloyd's Register of Shipping, London.

SURVEYOR TO

W. A. Robertson.  
LLOYD'S REGISTER OF SHIPPING  
BATAVIA

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."