

LLOYD'S REGISTER OF SHIPPING.

No. 4410B.

To be attached to Sba. report No. 4410.

Port of Sourabaya. Java;

16th of June, 1941.

THIS IS TO CERTIFY that

Joh. F. Vrouwes, - - - - -

the undersigned Surveyor to this Society did at the request of Messrs. N.V. Borneo Sumatra Handel Mij. "Lloyd's Agents" at this port, on the 25th day of April 1900afortyone and subsequent dates, examine the damage on board of the Dutch ss. "SINGKEP" of BATAVIA, 6607 tons gross. No. 83454 in Lloyd's Register Book 1940/41, alleged to have been sustained through a collision with ss. "THEMITOR" on the sixteenth day of December 1900aforty off Strone Point.

" For further particulars see ship's log."

Upon examination it was:

F O U N D
Shellplating starboard abreast No. 5 hatch sheerstrake, first, second and fourth strake below indented with frames and brackets in way bent; four port windows in way damaged. -----

Starboard forward and after side houses (W.C's & bathrooms) damaged. -----

Shellplating in way of forecastle indented. -----

De - Causing cable damaged in places. -----

RECOMMENDED

Sheerstrake plate first and second strake plates below to be removed, faired and refitted, fourth strake below plate to be faired in place; one frame in way to be cropped, -- faired and refitted, other frames to be faired in place; all brackets in way to be renewed. -----
Two port windows to be renewed, two to be closed up by steel plates. -

Forward side house topplating to be partly cropped and renewed; after sidehouse forward and side to be partly cropped and renewed. -----

First & second sheerstrake plates to be removed, faired and refitted; deckangle bar in way to be cropped; faired and refitted, frames in way to be faired in place; porthole-glasses to be made good. -----

De - Causing cable to be renewed. -----

(continued to page 2.)

This certificate is issued upon the terms of the Rules and Regulations as indicated on the original of this copy.

© 2020

Lloyd's Register
Foundation

005462-005464-0202-2

16th of June, 1941.

Continuation Damage report No.4410b, on the ss. "SINGKEP" of BATAVIA, 6607 tons

F O U N D

Bulwark and stanchions set in --
places. *****

Sheerstrakes and curtain plates;
bulwark and railing on bridge --
decks and boatdeck starboard ---
damaged. *****

Head Hawse pipe starboard -----
cracked. *****

R E C O M M E N D E D

Plating and railbar with stanchion
to be removed, faired and refitted
where necessary. *****

Sheerstrakes and curtain plates on
lower bridge deck to be renewed, or
boatdeck to be cropped and partly
and partly renewed; upper bridge
deck rails and stanchions to be
made good. *****



All piping and planking in way to
be removed for access and after-
wards refitted. *****

Crack in hawse pipe to be bored
off and doubling (2 sq.feet x 3"
to be fitted over crack. *****

These repairs have been carried out to my satisfaction, upon
completion tested where necessary and found in order. *****

A copy of this report has been sent to Lloyd's Register of Ship-
ping Office in London. - - - - -

Fee and expenses,.. .. F.190,00.
(Guilders; One hundred and ninety only)



© 2020

Lloyd's Register

005462-005462-0207