

FREEBOARD REPORT on the

"Hinsang"
Timber

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, ^{subject to}

1. the double bottom tanks were fitted within the midship half length of the steamer having adequate longitudinal subdivision (if this is not already the case, The plans are not available in this office at the time of report assignment) ✓
2. efficient provision being made for steering in the event of a breakdown in the main steering arrangements ✓
3. sup plates for lashings being riveted to the sheerstrakes at intervals of not more than 10 feet. the distance from an end bulkhead of a superstructure to the first eye-plate being not more than 6'-6" ✓
4. strong angle or metal sockets for securing the uprights being efficiently secured to the stringer plates. The lashing should not exceed ten feet

Timber.

Air Mail via U.S.A. ✓

31. 3. 41

S. B.

Lloyd's Register
Foundation

A. R.