

36433

Lloyd's Register of Shipping. 11 AUG 1941

Ship's Name "HIN SANG"

Official No. 172785

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in October 1940.

1. The sill, 12" high, on the Poop companionway leading to the upper deck made 18" high. ✓
2. A watertight steel hinged shutter fitted to ticket window on starboard side of bridge front bulkhead, capable of being securely fastened. ✓
3. Four automatic storm valves, with positive means of control, fitted to scuppers and discharges from spaces at aft end of combined bridge and poop, controlled from poop deck. ✓

Timber Freeboards.

1. Eyeplates for lashings riveted to the sheerstrake at intervals of not more than 10 feet, the distance from the end bulkheads of a superstructure to the first eyeplate being not more than 6'-6". ✓
2. Strong metal sockets for securing the uprights efficiently secured to the stringer plate, spaced 10 feet apart. ✓

W. S. Morrison

Vessel has adequate longitudinal sub-division in the double bottom space and secondary means of steering are provided.

W. S.
18/8/42

© 2021

Lloyd's Register
Foundation

005656-005670-0276

005656-005670-0276