

647830

STEWARTS and LLOYDS, LIMITED

1.19/936.

Messrs. Brown's Shipbuilding and Dry Dock Co., Ltd.,
 Line Street,
 HULL.

Order No. 21 of 30.9.42 and letter of 6.10.42.

Ship No. 11.

MAST made from steel tube in sections of dimensions as detailed,
 and swaged at joints when hot. Open at both ends.

1 Mast x 35ft. 6" long, comprising :-

- 1 - 9.1/2" o.d. x 5/16" thk. x 19ft. 6".
- 1 - 8.1/2" o.d. x 5/16" thk. x 9ft. 6".
- 1 - 7.1/2" o.d. x 5/16" thk. x 9ft. 6".

Tel. 18.

Tel. 18.

1 doubling 4ft. 0" long x 5/16" thk. shrunk on
 at derrick heel position.

1 doubling 3ft. long x 5/16" thk. shrunk on at hounds.

Mast to Lloyd's tests, requirements and inspection.

Mark: Ship No. 11.



D05756-00 5778-0158