

Steel sailing ship No. 192 proposed to be built by Messrs. N. Odero  
fu A at Sestri Ponente, with a view to class 100A1.

-----  
Rule dimensions ; 217.54 x 37.66 x 22.9

Equipment numeral ; 18354.  
-----

The anchors for this sailing vessel as required by Table 22  
of the Rules would be as follows:-

|                   |              |   |       |   |             |
|-------------------|--------------|---|-------|---|-------------|
| 1st. Bower anchor | 32 Cwts.     | + | stock | = | 40 Cwts.    |
| 2nd. " "          | 32 "         | + | "     | = | 40 "        |
| 3rd. " "          | <u>27½</u> " | + | "     | = | <u>34</u> " |
| Collective weight | 91½ Cwts     |   |       |   | 114 Cwts.   |

It is proposed as an alternative to supply stockless anchors  
in lieu of the above.

7  
It is submitted that if stockless anchors are supplied they  
should be increased 10%, as approved in previous similar cases, viz:-

|                   |              |            |
|-------------------|--------------|------------|
| 1st Bower Anchor  | 44 Cwts.     | Stockless. |
| 2nd " "           | 44 "         | "          |
| 3rd " "           | <u>37½</u> " | "          |
| Collective weight | 125½ Cwts.   |            |

FRI. OCT 25 1901

*L. J. 25/10/01*

*C.B.*

*Deferred till Tuesday*  
*WV*



© 2020

Lloyd's Register  
Foundation

005877-005889-0223