

Wood Vessel No.10 building by Messrs. Astilleros de Pasajes.


The Bilbao Surveyors state that the Wolverine 60 H.P.Motor which is now being fitted on board the above vessel was not built in accordance with this Society's Rules.

Plans of the pumping arrangements and of the oil fuel tanks have been submitted.

It is submitted the Bilbao Surveyors should be informed that the minimum diameter of the screw shaft which could be approved for this motor, having 3 cylinders $9\frac{1}{2}$ " dia. x 12" stroke, is $3\frac{3}{8}$ " unless fitted with a continuous liner, when the diameter might be reduced to $3\frac{1}{2}$ ". If the screw shaft now being fitted is $2\frac{1}{2}$ " diameter as stated in their letter, a new shaft of Rule size would require to be fitted or the Machinery could not be approved

Further they should state whether the motor has been opened out and all its parts thoroughly examined by them; the method of ignition; the diameter of the crank and intermediate shafts; the distance from centre to centre of the bearings on each side of the crank and whether there is a bearing between each crank; what means are proposed to ensure that leakage from the oil tanks will be kept clear of the wood framing and planking of the vessel; whether the oil tanks are provided with air pipes leading above deck with their upper ends turned down and fitted with gauze diaphragm, also (with reference to the starting petrol tank) if the requirements of Sec.4, para.6, of the Rules for internal combustion engines are being complied with; whether the water circulating pipe is provided with an efficient strainer inside the vessel and if a cock or valve has been fitted on the vessel's skin at the circulating water discharge line overboard; whether the exhaust pipe and silencer are water cooled or lagged to prevent damage by heat and what means are provided to prevent water being syphoned back to the engine through the overboard exhaust; whether a valve is fitted on the ship's side at the bilge pump discharge; and if the hand pump in the motor space can be worked from above the load water line.

They should also furnish a sketch giving the sizes and



006258-006271-0252 1/2

scantlings of the petrol starting tank and a plan of the stern tube.


It is concluded that this motor is being fitted on board for auxiliary purposes only and that the vessel's sail power will be maintained, the Surveyors should however be requested to confirm this.

With reference to the plan of oil tanks it is submitted that provided the tanks be constructed as amended and shown on the plan and be constructed under the usual conditions of survey and testing the plan merits approval.

The plans of pumping arrangements should be retained awaiting the required information.

Ln: - 6/6/18

J.P.R.


4.6.18.



© 2020

Lloyd's Register
Foundation