

COPY.

Lloyd's Register of Shipping.



Port of HULL.

3rd August, 1945.

F.R. PALMER,

J. STILEMAN,

and W.G. CONNELL,

This is to Certify that

the undersigned Surveyors to this Society did at the request of

Messrs. E. P. Atkinson & Son, of Goole survey the steamer "EMPIRE CONVOY" (ex "LEVENSAU") of London, formerly classed with the Germanischer Lloyd, on the 30th June, 1945 and subsequently, and that the following parts of Hull and Machinery were examined afloat and in drydock, viz:-

Holds and 'tween decks, bunkers, structure below boilers, peaks internally, machinery space, decks, casings, ash shoot, ventilators, hatchways, closing appliances, general equipment, steering gear examined generally and found in safe working condition. Vessel placed in dry dock, bottom and rudder cleaned and coated.

Machinery: Independent feed pump overhauled, screwshaft wear down $1/8$ ". Sea connections opened up, condenser tested. Air pump valves overhauled.

Boilers examined internally and externally with their mountings, doors and fastenings, examined under steam and the safety valves adjusted to a working pressure of 185 lbs./sq.in. The boilers are in a safe working condition.

The main and auxiliary engines, windlass and steering gear have been tried under steam and found satisfactory.

The electrical equipment has been examined but time did not permit for the necessary repairs, which will be done on return to this port.

and that we have transmitted to the Committee of Lloyd's Register of Shipping, London, a report stating that all repairs carried out by us have been completed to our satisfaction, and that we have recommended that she be assigned a record of "Examined L.R. 8,45" in the Register Book, indicating that, from the parts seen, she appears to be in an efficient condition for a period of twelve months from 3rd August, 1945.

F. R. Palmer *J. Stileman* *W. G. Connell*
SURVEYORS TO LLOYD'S REGISTER.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-
"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly performed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."