

Shell Indents.

Stem plate from 17 ft. to 27 ft. marks buckled (six indents)

Portside plating.

- B1 Two local indents in first and second frame spaces.  
E1 Slight local indent.  
F1 Badly indented in second frame space including upper seam.  
F7 One long indent fore and aft and one score mark.  
F8 One heavy score mark and three slight scores.  
F9 One heavy score mark approximately 12" long.  
G1 Badly indented in second frame space including lap and lower portion at stem.  
G4 Slight local indents (Eight in number)  
G5 Two slight indents in frame spaces and one on upper seam.  
G6 One local indent in second frame space from aft.  
G7 Five slight local indents and one heavy indent.  
G8 One heavy score mark and indent approximately 4 ft. long from lower to upper seams.  
G10 Four local indents.  
H5 Two local indents (one in plate centre and one in aft frame space)  
H6 Slight local indents (Five in number)  
H9 One local indent and one score mark.  
H10 Two slight indents.  
H11 Three slight indents aft.  
H12 Two slight indents and one score mark  
H13 Two heavy indents in aft spaces and badly scored at top landing  
H14 Slight indent in first space forward and various scores and shrapnel marks.  
H15 Various score marks and slight indents from shrapnel.  
H17 " " " " " "  
J6 Slight local indent at lower landing.  
J7 Slight local indent at lower landing forward end.  
J8 Slight local indent forward including frame.  
K6 Slight local indents and one heavy score mark  
K10 Slight " " upper landing in way of L10  
K13 Long score mark  
L10 Local indents and score marks  
L13 Score marks and one slight indent.  
M13 Bulwark plate indented in way of and including wash port door.

*marked as per enclosure.*



© 2021

Lloyd's Register  
Foundation