

S.S. "DÉPÔTÉ RENÉ REILLE"

Port Side

No 1 Plate in 6th Strake below Sheer removed and refitted

No 1 " " 7th " " " renewed to where it had been previously capped

No 1 " " 8th " " " removed faired and refitted

Starbd. Side

No 1 Plate in 7th Strake below Sheerstrake renewed to where it had been previously capped

No 1 Keel plate on being removed for the fitting of new stem was replaced by a new plate owing to it being considered inadvisable to work it into the vessel again as it had on a previous occasion being removed for effecting similar repairs, the rivet holes and caulking edge having suffered in doing so. *J.H.*

On completion of repairs the Fore Peak was tested. *J.H.*

When Anchors or Cables are supplied, the particulars are to be reported in the following form:—

ANCHORS.

Number of Certificate.	Anchors.*	WEIGHT, EX. STOCK.			WEIGHT OF STOCK.			TEST, PER CERTIFICATE.				WEIGHT REQUIRED by TABLE 30 or 31.			Description of Anchor.	Makers.	Where and when tested and Superintendent.
		Cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.	Tons.	Cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.			
35489	1st Bower ...	40	2	0	—	—	—	36	2	2	0	In accordance with			Stockless	Sykes	6th Oct. 22.20 Paul
34906	2nd "	36	0	0	—	—	—	33	2	2	0	with			"	"	17th Aug. 20 Paul
35600	3rd "	32	2	6	—	—	—	30	10	0	0	Mid Section			"	"	10th Nov. 20. Paul
	Collective Weight.	109	0	6													
35586	Stream	10	0	6	2	2	6	12	0	0	0	1/2	0	0	8m Stock	"	Oct. 30. 20 Paul
35585	Kedge.....	4	2	20	1	1	12	7	0	0	0	1/2	0	0	"	"	" " " Paul

* When a bower anchor is supplied it must be clearly stated whether it is a 1st, 2nd, or 3rd bower.


CHAIN CABLES.

Number of Certificate.	Length and size supplied.		Test per Certificate.		WEIGHT OF CHAIN CABLE.		Length and size per Table 30 or 31.		Description.	Makers of Cables.	When and where tested and Superintendent.
	Length.	Diam.	Statutory.	Breaking.	Supplied.	Per Table 30 or 31.	Length.	Diam.			
	Fathoms.	Ins.	Tons.	Tons.	Cwts. qrs. lbs.	Cwts. qrs. lbs.	Fathoms.	Ins.			
31294	210	1 3/4	55.125	77.125	34.2	34.2	In accordance with		Steel	Richard Sykes & Co	Nov 25. 1920 B.H. Paul
30616	30	1 3/4	55.125	77.125	47.3	47.3	with mid. section		"	"	Aug 28 " " " JA Ref.
	Iron Stream Chain or Steel Wire...										

The following equipment has also been examined aboard the vessel and 90 fms 4" Steel wire (102^{lbs}) Towline } These are in accordance with the midship section
 90 fms. 3^{1/2}" " " (79^{lbs}) mooring }
 3 coils steel wire 2^{3/8}" (54^{lbs}) "
 1 coil " " 2^{3/8}" (54^{lbs}) " *J.H.*

N.B.—If this Report is copied by Copying Press, especial care must be taken that the copying paper is not so much damped as to spread the ink, or to cause it to show through to the other side.

THE SURVEYORS ARE REQUESTED NOT TO WRITE ACROSS THIS MARGIN.



© 2021

Lloyd's Register Foundation