

00666 - 006679 - 0147 1/2

50,914.

F.E.

Received by Chief Ship Surveyor .....

Received from Chief Ship Surveyor .....

VESSEL'S NAME Steel S.S. "YPRES MARU". Rpt. Kob. No. 2994.

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement." - Extract from Sub-Committee's Report, 24/5/92.)

Transverse No. 83.17 Depth "d" 15.92

Framing: Table No. 3 Description Bulb angle

Longitudinal No. 35347

Proportions Length = 11.33  
Depth =

Shelter / Deck Sheerstrake as approved.


This vessel appears to have been built in accordance with the Rules and the approved plans, and it is submitted she is eligible to be classed as 100 A.1. (Steel) Shelter Deck with freeboard," as recommended. The Summer freeboard of 9' - 3 1/2" from centre of disc to top of statutory deck line at Shelter deck, now marked on the vessel's sides, to be inserted in the classification certificate, and recorded in the Register Book, and further, the remaining freeboards, as shown on the accompanying verification form to be inserted in the certificate of classification.

2 Dks. (Steel) and Shelter Dk. (Steel).

Cell. D.B. 366', 1153t. D.T.a. 39', 936t. FPT. 153t. APT. 72t.

F.K. Collision BH. to Shelter Dk. 6 BH. to upper dk. pt. cen.

A. & C.P.



The Surveyors should state whether the reversed frames  
in E. and B. space and forward are 6" x 3½" x .40 and 5" x 5" x .50  
as shewn on profile as built, ~~or~~ 5" x 5" x .50 and 5" x 3½" x .44  
respectively, as given on the report.

-----

*M*



© 2021

Lloyd's Register  
Foundation

0147 2/2