


# S. S. N° 478.

LENGTH B.P. 400-0, BREADTH EXT. 52-0, DEPTH MLD. 30-0.



ANG. FRAMES 6 x 3 1/2 x 38, 6' REVERSI 3 x 3 1/2 x 38 OR BULB ANG 7 x 3 1/2 x 44 SPACED 24 APART. ALL PLATE TO UPPER DECK.

BULKHEAD N° 12 NUMERALS 30 TO 32 PLATING 5 x 5 x 3/4 FRAME 4 x 4 x 38 TO DECK. B.A. STIFFERS 10 x 3 1/2 x 52 BULB ANG 2-6 APART 8' 3 1/2 x 50 2-6 APART 8' STIFFERS HORIZONTAL AS SHOWN.

BULKHEAD N° 42 NUMERALS 28 TO 30 & 19 TO 20 PLATING 5 x 5 x 3/4 FRAME 5 x 5 x 38 DECK ANGLES 4 x 4 x 36 HOLD STIFFERS 10 x 3 1/2 x 52 BULB ANG 2-6 APART TWEEN DECK 4 x 3 x 34 ANG OR 5 PLATES 2-6 APART.

BULKHEADS N° 74 & 97 NUMERALS 26 TO 28 & 18 TO 19 PLATING 5 x 5 x 3/4 FRAME 5 x 5 x 38 DECK ANGLES 4 x 4 x 36 HOLD STIFFERS 9 x 3 1/2 x 54 B.A. 2-6 APART TWEEN DECK 4 x 3 x 34 ANG OR 5 PLATES 2-6 APART.

BULKHEAD N° 145 30 TO 32 & 21 TO 22 PLATING 5 x 5 x 3/4 FRAME 5 x 5 x 38 DECK ANGLES 4 x 4 x 38 HOLD STIFFERS 10 x 3 1/2 x 64 B.A. 2-6 APART TWEEN DECK 4 x 3 x 34 ANG OR 5 PLATES 2-6 APART.

BULKHEAD N° 175 FRAME 6 x 6 x 56 NUMERALS 34 TO 36 PLATING 4 x 4 x 30 NUMERALS FOR STIFFERS 34 TO 36 & 19 TO 20. 10 x 3 1/2 x 64 B.A. 24 APART. 2 HORIZONTAL STIFFERS AT LINE OF STRINGERS 10 x 3 1/2 x 64 B.A. IN LIEU OF 8 x 3 1/2 x 44 B.A. 4-0 APART.





J L Thompson & Son

No 478

S S "Tervier".

Profile as built.

SLA 24719

1/n "RYUNAN MARU."



© 2020

Lloyd's Register  
Foundation

006723-006730-0131