


FREEBOARD REPORT on ~~the~~ Swan Hunter's No 1420

Dims: - 245' x 37.5' x 21.0'

Fixed moulded draught desired = 14'-10½" (15'-0" to B.K.) ^{Builders}

(1) The equivalent depth moulded of a full scantling Flush deck ship with 50% excess sheer, to give a moulded draught of 14'-10½" for all seasons = 17'-11"

(2) The equivalent moulded depth of a full scantling ship with actual erections (75.5% correct) and 50% excess sheer, to give a moulded draught of 14'-10½" for all seasons = 16'-0"

Copy to Mr Potts


19.10.31.

Length of Ship

Corresponding percentage {
(Para. 11, 12, 13, or 14) }

Indian Summer " " "

N. A. Winter " " "

© 2021

Lloyd's Register
Foundation

006731-006740-0052