

No 1420 SHIP

16th October, 1931.

~~725.~~~~passenger and cargo steamer.~~Preliminary Freeboard Particulars.

Moulded dimensions:- 245'0" P.P. x 37'6" mld x 21'0" Mld to upper dk.

Approx. under deck tonnage

1350 tons.

Sheer fwd. 4'6"

Sheer $\frac{1}{8}$ th length fwd. 2'8 $\frac{1}{2}$ ".

" aft 1'6"

" $\frac{1}{8}$ th " aft 8"Drop of sheer abaft amidships 1 $\frac{1}{4}$ "

Lowest point of sheer 25'-0" aft of midships.

Sheers are measured on upper deck above the moulded depth amidships.

Camber on upper deck

9 $\frac{1}{2}$ "

Erections:-

Combined poop and bridge 160'0" x 7'6"

Fore end
closed by steel
bulkhead.

Forecastle

25'0" x 7'0"

Open at aft end.

$$\begin{array}{r} 160 \\ 75 \\ \hline 185 \\ 245 \end{array} = .755$$


© 2021

Lloyd's Register
Foundation

006731-006740-0053