

Gun 7

Sample Report

2<sup>nd</sup> SPECIAL SURVEY No. 1.....

Due 8.34

Vessel placed in drydock, bottom, rudder, stern frame, <sup>BAR</sup> keel and stem examined and found or put in good condition and afterwards recoated.

Hold<sup>accumulation recess</sup>, tween decks, <sup>cross and wing</sup> fore and after peaks, engine and boiler spaces and <sup>cross and wing</sup> coal bunkers cleared for survey; ceiling lifted as required by the Rules, all oxidation removed from all parts, and all steelwork throughout all parts of the vessel carefully examined and found or put in good condition and afterwards recoated. Lining on ship's side removed in way of sidelights, plating in way of same examined and found or put in good condition. ~~Double bottom tanks, fore and after peak tanks,~~ Deep tank<sup>and oil fuel bunkers</sup> examined internally and tested as required by the Rules. Decks, hatchways, <sup>COAL SCUTTLES.</sup> ~~patches,~~ <sup>VENTILATOR COPINGS</sup> ~~fore and~~ ~~after,~~ ceiling, cargo battens, air and sounding pipes, plates under sounding pipes, windlass, steering engine, gear rods, chaines, sheaves etc., pumps, ~~sluice valves,~~ ~~watertight doors,~~ scuppers, skylights, boats, mast<sup>(wedges removed)</sup>, spars, rigging, anchors, chain cables (cables ranged), hawsers and warps and general equipment examined and all found or put in good condition; ~~Freeboard verified.~~

NOTE. The outside plating may require to be drilled, but if it is not drilled the Surveyors must state that in their opinion drilling is not necessary.



© 2020

Lloyd's Register  
Foundation

006809-006818-0055

006809-006818-0057